



Walter J Barnes Electric
PO Box 10458, Jefferson, LA 70181
(504) 835-1756

Nov 19, 2024
Quote # 24-1018

Contact

Riverfront line
Canal, New Orleans, Louisiana 70181

Reinstall rail bonds

1. We will reinstall rail bonds per the drawing provided.
2. We will install 1- 2" sch 40 PVC per run to each rail bond. These conduits will be poured in roughly a 6"x6" concrete envelope up to the bond termination.
3. RTA will excavate all trenches and reinstall any backfilled material, including rock. Any Track leveling required after excavation is to be done by the RTA.
4. We will provide all conduit, wire, and rail bonds.
5. We require full track closure in the area. We anticipate this will take approximately 15 working days. this time does not include time spent by RTA excavating the area.
6. Our Price is based on a 6-day-10-hour-a-day schedule.
7. We have not included any protection of the steel bond plates.

Quote Total	\$148,400.00
--------------------	---------------------

Clarifications to Scope:

01. We have seen (0) addenda.
02. Our price does not include any temporary power or lighting.
03. Our price includes sales tax.
04. Our price is based on working a standard 6/10 workweek. Our price does not include any Sunday or Holiday work.
05. Our price does not include third party testing.
06. Our pricing is based on today's market commodity prices. Due to the COVID-19 pandemic and the volatility of the current market, we unfortunately cannot hold pricing of materials. Fluctuations in material prices may produce a change order to the project. The availability of materials is also unknown. While we and our subcontractors will make every reasonable effort to provide delivery of materials to meet the current schedule of this project, it is expected that there may be delays in the shipments of materials which could affect the completion date of this project.

Standard Exclusions:

01. Our price does not include work not indicated on the electrical drawings.
02. Our price does not include cost of bond. If needed, please add 1.1% to our price.
03. We do not include any engineering fees.
04. Cutting and patching of concrete or asphalt will be by others.
05. Our price does not include spoils removal.
06. Special compaction will be by others, if required. We will provide normal tamping only for our trenching.
07. Removal of underground obstructions will be by others.
08. Traffic control will be by others.

Qualifications:

01. This quotation is valid for a period of (30) days from the above date.
02. Terms of payment are NET30 with maximum of ten (10%) percent retainage withheld.
03. This proposal includes prompt payment of all stored and/or installed material on job site. These costs will be reflected on the monthly progress billings.
04. All material to be furnished by others, will be supplied to a site or area selected by WJBE, in a timely manner and with sufficient quantities to meet the requirements of the project scope and schedule. All costs incurred with regards to material quantities and/or receipt dates will be for the buyer's account.
05. WJBE shall not be held liable for errors or omissions in the designs of others, nor inadequacies of materials and equipment specified or supplied by others.
06. WJBE shall not be liable for indirect loss or damage.
07. All costs and/or man-hour breakdown lists included in this proposal are provided for accounting purposes only. This information is not intended as a basis for partial award.
08. Anything (verbal or written) expressed or implied elsewhere, which is contrary to these conditions shall be null and void.

I appreciate the opportunity to provide you with this quotation. Please call (504.835.1756) or email (estimating@wjbe.com) if you have any questions or require further information.

Regards,
WALTER J BARNES ELECTRIC CO INC

Nick Gagliano